BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

BBMP/2013-14/RD/WORK_INDENT9186

Providing Pot hole filling in ward No. 8, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN	
				In Figures	Rates In Words
1	343.00	KSRRB- M 3000-2: Making up loss of of Material/irregulatities on shoulder ot the design level by adding fresh approved soil and compacting it with appropriate equipment complete as per s[ecifications. MORTH Specification No. 3003 (Page No. 265/ Item No. 35.2) SR 2013-14	Sqm	16.31	Rupees Sixteen and Thirty One Paise Only
2	128.00	KSRRB M400-17 : Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material of tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifcations. MORTH Specification No. 406 (Page No. 170 & Item No. 20.18) SR 2013-14	Cum	1121.04	Rupees One Thousand One Hundred Twenty One and Four Paise Only
3	853.30	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2, Complete as per specifications. MORTH Specification No. 3004.2 (Page No. 265 & Item No. 35.5) SR 2013-14	Sqm	410.40	Rupees Four Hundred Ten and Forty Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92